


[illegible]

Job WESTMINSTER HALL CONSERVATION PROJECT		Scale C
Title NORTH WALL INTERNAL ELEVATION		No 2002
Proposed Repair Works		Rev H
Scale (A1) 1:	50	H

	Remove existing loose or disfiguring mortar and re-point as C42/506 using lime mortar to match approved sample as Z21.
	Remove loose surface with a stiff bristle brush as C42/120. Brush back to sound surface and seek further instructions.
	Very carefully remove dust and loose material with a soft bristle brush and vacuum cleaner, taking care not to dislodge any of the original tooled surface of the stonework still adhering.
	Clean stone surfaces using a single application of Arte Mundit V, as C40/500-510. A secondary application of Laponite may be required and will be instructed by the PM if necessary.
	~~Cut-out decayed or damaged area of existing stone and repair with stone indent.~~
	<i>Hatches no longer in use</i>
	~~Cut-out existing stone in its entirety and replace with new stone.~~
	Cracks in existing stonework to be repaired as annotated.

GENERAL REPAIR NOTES	
1.	Refer to carved stonework repair schedule for works to the frieze, label stops and heraldic beasts.
2.	Remove hard mortar pointing generally to window arch, including moulded stonework and to reveal. Re-point in lime mortar according to specifications.

ANNOTATION KEY	
1.00	Chilmark full stone replacement
2.00	Chilmark stone indent
3.00	Bath Stone full stone replacement (N.B. stone indent to transom)
4.00	Bath Stone indent
5.00	Plastic Repair

